

執行預算

統計分析  數量比率  金額比率

項次	工程項目	單位	合約數量	合約單價	合約金額	預算數量	預算單價	預算金額	採購數量	採購金額	日報表數量	日報表金額	計價數量	計價金額		
壹	游泳池工程	式	0.0	0	0	0.0	0	0	0.0	0	0.0	0	0.0	0		
一	過濾設備工程	式	0.0	0	0	0.0	0	0	0.0	0	0.0	0	0.0	0		
01	游泳池循環過濾系統		0.0	0	0	0.0	0	0	0.0	0	0.0	0	0.0	0		
02	石英砂過濾桶 D=1200mm*1500mmH	座	2.0	243,600	487,200	2.0	203,000	406,000	2.0	40,000	1.0	20,000	2.0	40,000		
03	不銹鋼避震軟管 3"	式	3.0	9,180	27,540	3.0	7,650	22,950	3.0	22,950	3.0	22,950	3.0	22,950		
04	循環過濾泵 5HP	台	3.0	36,984	110,952	3.0	30,820	92,460	3.0	92,460	3.0	92,460	2.0	61,640		
05	微電腦水質自動偵測器	台	1.0	142,500	142,500	1.0	118,750	118,750	1.0	118,750	1.0	118,750	1.0	118,750		
06	自動加藥機 PH、CL各1	台	2.0	14,250	28,500	2.0	11,875	23,750	2.0	23,750	2.0	23,750	2.0	23,750		
07	加藥桶 500公升含計量錶	只	2.0	9,600	19,200	2.0	8,000	16,000	2.0	16,000	2.0	16,000	2.0	16,000		
08	藥水	公升	1,000.0	14	14,400	1,000.0	12	12,000	1,000.0	12,000	800.0	9,600	900.0	10,800		
09	游泳池出水 2" 平面出水口 ABS	只	19.0	780	14,820	19.0	650	12,350	19.0	12,350	19.0	12,350	10.0	6,500		
10	溢水溝 ABS 20cm 縱向溢水	米	80.0	1,020	81,600	80.0	850	68,000	80.0	68,000	80.0	68,000	40.0	34,000		
11	90° 轉角板 ABS	片	4.0	3,570	14,280	4.0	2,975	11,900	4.0	11,900	4.0	11,900	4.0	11,900		
12	壓條 PVC	米	160.0	216	34,560	16.0	180	2,880	16.0	2,880	16.0	2,880	10.0	1,800		
13	游泳池中程迴流吸塵頭 SP-1026 ABS	只	4.0	612	2,448	4.0	510	2,040	4.0	2,040	2.0	1,020	4.0	2,040		
14	電動式過濾桶用控制閥 SUS304 3"	只	10.0	10,200	102,000	10.0	8,500	85,000	10.0	85,000	5.0	42,500	6.0	51,000		
15	一切凡而及另料	式	3.0	10,800	32,400	3.0	9,000	27,000	3.0	27,000	3.0	27,000	4.0	36,000		
16	泳池三階爬梯 SUS#316 AS05477	只	4.0	9,600	38,400	4.0	8,000	32,000	4.0	32,000	2.0	16,000	4.0	32,000		
17	過濾用高級濾材:無煙煤、石英砂、石榴石、支層	式	2.0	36,000	72,000	2.0	30,000	60,000	2.0	60,000	2.0	60,000	2.0	60,000		
18	程式控制	式	1.0	38,400	38,400	1.0	32,000	32,000	1.0	32,000	1.0	32,000	1.0	32,000		
20	除毛器 SUS304 3" 含洩氣閥	只	3.0	12,000	36,000	3.0	10,000	30,000	3.0	30,000	1.0	10,000	3.0	30,000		
21	消波繩 25M	條	7.0	14,400	100,800	7.0	12,000	84,000	7.0	84,000	3.0	36,000	4.0	48,000		
22	水道消波繩收納箱	座	7.0	35,700	249,900	7.0	29,750	208,250	7.0	208,250	3.0	89,250	5.0	148,750		
23	固定式起跳台	座	6.0	24,000	144,000	6.0	20,000	120,000	6.0	120,000	2.0	40,000	4.0	80,000		
24	仰泳轉身標誌桿	組	2.0	24,000	48,000	2.0	20,000	40,000	2.0	40,000	1.0	20,000	2.0	40,000		
25	SUS304 1T 平衡水箱 4t	只	1.0	57,600	57,600	1.0	48,000	48,000	1.0	48,000	1.0	48,000	2.0	96,000		
26	一切機器固定座及防震基礎(不含RC)	式	3.0	15,000	45,000	3.0	12,500	37,500	3.0	37,500	1.0	12,500	2.0	25,000		
27	掛勾座 SUS316	只	14.0	3,570	49,980	14.0	2,975	41,650	14.0	41,650	5.0	14,875	6.0	17,850		
28	水質顯示看板(PH、CL2、溫度、時間)	式	1.0	86,400	86,400	1.0	72,000	72,000	1.0	72,000	1.0	72,000	2.0	144,000		
29	設備運吊搬運工事	式	1.0	10,800	10,800	1.0	9,000	9,000	1.0	9,000	1.0	9,000	0.0	0		
30	設備按裝及機房配管工資	式	1.0	98,563	98,563	1.0	82,136	82,136	0.0	0	0.0	0	0.0	0		
二	清潔保養設備		0.0	0	0	0.0	0	0	0.0	0	0.0	0	0.0	0		
01	清潔設備(含吸塵頭、推桿、軟管、撈葉網)	套	1.0	14,400	14,400	1.0	12,000	12,000	1.0	12,000	1.0	12,000	1.0	12,000		
					2,202,643						1,809,616					
											1,361,480					
											940,785					
											1,202,730					